

AD-A075 890

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/G 13/2
NATIONAL DAM SAFETY PROGRAM. NEW ROCHELLE RESERVOIR NUMBER 3 DA--ETC(U)
SEP 79 G KOCH DACW51-79-C-0001


UNCLASSIFIED


1 OF 2

AD-A075890



NL





NATIONAL BUREAU OF STANDARDS
MICROCOPY RESOLUTION TEST CHART

REPORT DOCUMENTATION PAGE

READ INSTRUCTIONS
BEFORE COMPLETING FORM

1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report New Rochelle Reservoir No. 3 Hutchinson River Basin, Westchester County, NY Inventory No. NY 110		5. TYPE OF REPORT & PERIOD COVERED Phase 1 Inspection Report National Dam Safety Program
7. AUTHOR(s) George Koch, P.E.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York State Department of Environmental Conservation/ 50 Wolf Road Albany, New York 12233		8. CONTRACT OR GRANT NUMBER(s) DACW-51-79-C-0001
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Conservation/ 50 Wolf Road Albany, New York 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza/ New York District, CofE New York, New York 10007		12. REPORT DATE 4 Sep 1979
		13. NUMBER OF PAGES
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		15. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability New Rochelle Reservoir No. 3 Westchester County		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. New Rochelle Reservoir No. 3 did not reveal any conditions which pose an immediate threat to life or property. Additional studies recommended. It has been determined that the embankment would be overtopped for all storms exceeding 35% of the PMF. Significantly dangerous water surface levels could		

DA 075890

DDC FILE COPY

20. (Continued)

→ be reached downstream of the dam if the embankment is completely breached. Consequently, the dam is assessed as unsafe, non-emergency (SEE REPORT ASSESSMENT). An emergency operation plan, warning system, and surveillance should be implemented as remedial measures are completed. Minor deficiencies exist. ↗

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

HUTCHINSON RIVER BASIN

NEW ROCHELLE RESERVOIR NO. 3

WESTCHESTER COUNTY, NEW YORK
INVENTORY NO. N.Y. 110

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM



APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED
CONTRACT NO. DACW-51-79-C0001

NEW YORK DISTRICT CORPS OF ENGINEERS

MARCH, 1979

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or special
A2W	

79 10 31 027

HUTCHINSON RIVER BASIN
NEW ROCHELLE RESERVOIR NO. 3 DAM
I.D. No. N.Y. 110
Phase I Inspection Report

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	
- OVERVIEW PHOTOGRAPH	
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	3
2 ENGINEERING DATA	4
2.1 DESIGN	4
2.2 CONSTRUCTION RECORDS	4
2.3 OPERATION RECORD	4
2.4 EVALUATION OF DATA	4
3 VISUAL INSPECTION	5
3.1 FINDINGS	5
3.2 EVALUATION OF OBSERVATIONS	6
4 OPERATION AND MAINTENANCE PROCEDURES	7
4.1 PROCEDURE	7
4.2 MAINTENANCE OF DAM	7
4.3 WARNING SYSTEM IN EFFECT	7
4.4 EVALUATION	7

	<u>PAGE NO.</u>
5 HYDROLOGIC/HYDRAULIC	8
5.1 DRAINAGE AREA CHARACTERISTICS	8
5.2 ANALYSIS CRITERIA	8
5.3 SPILLWAY CAPACITY	8
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	9
6 STRUCTURAL STABILITY	10
6.1 EVALUATION OF STRUCTURAL STABILITY	10
7 ASSESSMENT/RECOMMENDATIONS	11
7.1 ASSESSMENT	11
7.2 RECOMMENDED MEASURES	11

APPENDIX

A. PHOTOGRAPHS	
B. ENGINEERING DATA CHECKLIST	
C. VISUAL INSPECTION CHECKLIST	
D. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS	
E. REFERENCES	
F. DRAWINGS	

PHASE 1 REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	New Rochelle Reservoir No. 3 Dam I.D. No. NY 110 (#215-1336)
State Located:	New York
County:	Westchester
Watershed:	Hutchinson River Basin
Stream:	Hutchinson River
Date of Inspection:	November 16, 1978

ASSESSMENT

Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, additional studies should be undertaken to further evaluate conditions affecting the dam.

Additional hydrologic investigations are required to more accurately determine the site specific characteristics of the watershed. Using the Corps of Engineer's Screening Criteria for initial review of spillway adequacy, it has been determined that the embankment would be overtopped for all storms exceeding approximately 35% of the PMF (Probable Maximum Flood). A flood wave analysis, assuming a complete breaching of the embankment, indicates that water surface levels downstream of the dam could reach levels which would pose significant danger to residents. The spillway is, therefore, adjudged as seriously inadequate and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam.

It is, therefore recommended that within 3 months of the date of notification of the owners, a hydrologic investigation of the structure should be undertaken to determine the appropriate mitigating measures to be taken. Within 18 months of the date of notification, appropriate remedial measures should be completed. In the interim, a detailed emergency operation plan and warning system should be developed and

around-the-clock surveillance should be provided during periods of unusually heavy precipitation. In addition, all stoplogs should be removed to provide increased spillway capacity.

There are also several minor deficiencies on this structure which should be corrected. The trees and brush on the embankment should be cut and the gully on the downstream face should be filled in. The gunite on the spillway should be patched. Finally, the reservoir drain control rod should be repaired and the drain made operational. These actions should be taken within 6 months of the date of notification of the owner.

George Koch

George Koch
Chief, Dam Safety Section
New York State Department
of Environmental Conservation
NY License No. 45937

Approved By:

Clark H. Benn

Col. Clark H. Benn
New York District Engineer

Date:

4 Sept 79



OVERVIEW

NEW ROCHELLE RESERVIOR No. 3 (N.Y. 110)

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
NEW ROCHELLE RESERVOIR No. 3
I.D. No. NY 110
(#215-1336)
HUTCHINSON RIVER BASIN
WESTCHESTER COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase 1 Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of the Dam and Appurtenant Structures

The New Rochelle Reservoir No. 3 Dam consists of an earth embankment with a concrete chute spillway passing through the center of the dike.

The embankment is approximately 30 feet high and 450 feet long. The crest is about 6 feet wide. The plans indicate that a core wall extends the length of the embankment. The upstream slope is 1 vertical on 2 1/2 horizontal. The downstream slope is 1 vertical on 2 horizontal.

The spillway, which is in the center of the embankment, was reconstructed in 1949. It now consists of a concrete chute spillway, 34 feet wide. A three span bridge carrying a bridle path, runs along the crest of the dam and crosses the spillway channel. Two pointed nosed piers are located in the spillway. There are provisions for up to two feet of concrete stoplogs on each of the two outside spans.

Beyond the rounded crest, the spillway chute proceeds down on a 1 vertical on 1 1/2 horizontal slope to the stream channel. The downstream slope consists of stone paving covered with 3 inches of gunite. The channel, which is concrete lined in this area, then passes under a ramp, under the Hutchinson River Parkway, and then into the natural stream channel.

A 42 inch diameter cast iron drain pipe is shown on the plans. The pipe outlets near the base of the spillway channel. A inclined valve control rod extends from a point on the upstream slope out into the reservoir. This valve rod may be presumed to control a 24 inch valve which is at the inlet to the drain pipe. While the 42 inch pipe has a plug at the inlet end, it is not known whether this could be easily removed. Therefore, the inlet to the drain is controlled by the 24 inch inlet.

b. Location

The New Rochelle Reservoir No. 3 Dam is located on the southern end of the reservoir. The boundary line separating the City of New Rochelle from the Town of Eastchester runs through the dam. Reservoir No. 3 is the middle of the three reservoirs which are within a mile of one another on the Hutchinson River.

c. Size Classification

This dam is 31.5 feet high and the reservoir has a storage capacity of 230 acre feet. Therefore, the dam is in the small size category as defined by the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification

The dam is classified as "high" hazard due to the presence of the Hutchinson River Parkway immediately downstream of the dam. In addition, there are a number of homes downstream of the dam, and a number of homes beyond the point where the stream passes under the parkway.

e. Ownership

This dam is now owned by Westchester County and under the jurisdiction of the County Department of Parks, Recreation and Conservation. Mr. John Fava (914-682-2616) is the Director of Park Facilities for Westchester County.

f. Purpose of Dam

The dam was originally constructed to provide water to be used by the New Rochelle Water Company. The dam was turned over to the county around 1920 and is now used to maintain the water surface for recreational purposes.

g. Design and Construction History

Based on the records available, the dam was built in 1908 by the New Rochelle Water Company. After Westchester County took over the dam, extensive renovations were made to the spillway in 1949. The changes made were based on plans prepared by the Westchester County Department of Public Works.

h. Normal Operating Procedures

Water flows over an ungated spillway. The level of the reservoir may be varied by 2 feet by the addition or removal of concrete stoplogs.

1.3 PERTINENT DATA

<u>a. Drainage Area</u> (acres)	1826
<u>b. Discharge at Dam</u> (cfs)	
Total (Spillway with no stoplogs) at Maximum High Water	1815
Spillway with 2 ft. of stoplogs in place at Maximum High Water	1357
Reservoir Drain at Spillway Crest Elevation	37
<u>c. Elevations</u> (Based on USGS Datum)	
Top of dam	130.5
Spillway Crest	123.0
Invert Reservoir Drain Inlet	101.8
<u>d. Reservoir</u> (acres)	
Surface Area at top of dam	47.4
Surface Area at spillway crest	27.5
<u>e. Storage Capacity</u> (acre-feet)	
Top of Dam	498
Spillway Crest	220
<u>f. Dam</u>	
Embankment Type: Earthfill with corewall	
Embankment Length (ft)	450
Slopes (V : H) Upstream	1: 2.5
Downstream	1:2
Crest Elevation	130.5
Crest Width (ft)	6
<u>g. Spillway</u>	
Type:	Concrete chute with two piers supporting small bridge crossing spillway in center of channel. Provisions for up to 2 feet of concrete stoplogs under the two outside spans.
Length: (ft) Weir	34.0
<u>h. Reservoir Drain</u>	
Type:	42 inch diameter cast iron pipe with a 24 inch diameter pipe and valve controlling the inlet.
Control:	Mechanically operated valve with stem extending up to point on upstream slope.

SECTION 2: ENGINEERING DATA

2.1 DESIGN

a. Geology

The New Rochelle Reservoir No. 3 Dam is located in the Manhattan Hills section of the New England Uplands physiographic province of New York State. This province consists of low hilly terrain of gentle relief. The bedrock in the area, formed during the Cambrian and Ordovician eras has been intensely metamorphosed, heavily injected and re-crystallized. Shale, slate, schist, gneiss and quartzite are among the types of rock in this area. The surficial soils are the result of glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation.

b. Subsurface Information

No records from subsurface investigations which may have been made at the time of construction of this dam were available. The only information which was available was from the 1915 New York State Conservation Commission inspection report which states that the dam is founded on rock.

2.2 CONSTRUCTION RECORDS

No construction records were available from the original construction of this structure. However, the spillway was extensively rehabilitated in 1949 and a complete set of the contract plans, prepared by the Westchester County Department of Public Works, were available.

2.3 OPERATING RECORDS

There were no operating or water level records available for this structure.

2.4 EVALUATION OF DATA

The data presented in this report was obtained from the Department of Environmental Conservation files. While only limited data was available concerning the subsurface conditions, overall, the information available appears to be adequate and reliable for the purpose of the Phase 1 inspection.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of the New Rochelle Reservoir No. 3 Dam was conducted on November 16, 1978. The weather was clear and the temperature was around 40° F. Water was flowing over the spillway at a depth of approximately 6 inches at the time of the inspection.

b. Embankment

The embankment was in satisfactory condition. There were no indications of sloughing, subsidence, or movement.

The upstream face was covered with riprap. A number of small trees were growing through the riprap on this face. A bridle path crossed along the crest of the dam and so there was no vegetation on the crest. Light brush and vines were growing on the eastern end of the downstream slope. A small gully up to 2 feet deep running along the edge of the eastern spillway wall has been formed by surface runoff from the crest. About half the area to the west of the spillway was covered with grass. The grass had been mowed and the section was in good condition except for a path which had been worn into the slope. The area on the downstream slope nearest the west abutment was overgrown with large trees and brush. There was a low area beyond the western end of the embankment.

c. Spillway

The spillway was in satisfactory condition. It was reconstructed in 1949 and a bridge for the bridle path was added across the top sometime after 1972. The concrete surfaces were in good condition with the exception of one area on the downstream slope of the spillway channel. A layer of gunite had peeled off of a section which was approximately 10 feet long and 10 feet wide.

There are provisions for stoplogs under two of the three spans of the bridge. At the time of the inspection, three concrete stoplogs (1 foot total) were in place under the western span and 4 logs (1.4 feet) in under the eastern span. All of the logs in place were in good condition.

d. Reservoir Drain

Visual observations of the reservoir drain were limited to inspection of the outlet and the valve control rod on the upstream slope. The drain outlets at the base of the spillway channel. A log was lodged in the semi-circular opening for the drain outlet. The valve control rod was bent and the frame supporting the rod was in need of repair.

e. Downstream Channel

The channel beyond the end of the spillway is lined with concrete for several hundred feet. The channel passes under bridges for a bridle path, a highway ramp, and the Hutchinson River Parkway before re-entering the natural channel. The concrete in the channel was in good condition.

EVALUATION OF OBSERVATIONS

Visual observations did not reveal any serious problems which would affect the immediate safety of the dam. However, the following deficiencies were noted:

- a. Trees and brush growing on dam should be cut.
- b. The section on the spillway where the gunite has come off should be repaired before it deteriorates further.
- c. The gully adjacent to the eastern wall of the spillway should be filled in and regraded.
- d. The reservoir drain control rod should be repaired and the drain made operational.

SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURE

The normal water surface elevation is at the crest of the spillway. The water surface may be varied by the addition or removal of up to 2 feet of concrete stoplogs. The reservoir provides 278 acre-feet of storage between the crest of the spillway and the top of the dam.

4.2 MAINTENANCE OF DAM

The spillway was reconstructed in 1949. It appears that routine maintenance such as mowing the grass is performed on this structure at regular intervals. However, the brush and trees which are growing on the dam in several locations should be cut.

4.3 WARNING SYSTEM IN EFFECT

No apparent warning system is present.

4.4 EVALUATION

All brush and trees growing on the dam embankment should be cut and a regular inspection and maintenance program should be implemented to keep the embankment relatively clear. In addition, the reservoir drain should be made operational and checked periodically.

SECTION 5: HYDROLOGIC/HYDRAULIC

5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the contributing watershed to New Rochelle Reservoir No. 3 was made using the USGS 7.5 minute quadrangle sheet for Mount Vernon, N.Y. The watershed consists of a heavily developed urban area and a lightly wooded area, some of which has been developed into a residential section. Relief ranges from flat to moderate.

New Rochelle Reservoir No. 1 is less than a mile upstream of this structure, so the drainage area for Reservoir No. 3 encompasses the drainage area for the upstream reservoir as well. The size of the rectangularly shaped drainage area for Reservoir No. 3 is 1826 acres, which includes the 1292 acres which form the watershed for Reservoir No. 1.

5.2 ANALYSIS CRITERIA

No hydrologic/hydraulic information was available regarding the original design for this dam. Therefore, the analysis of the spillway capacity of the dam was performed using the Corps of Engineers HEC-1 (Dam Break Version) computer program; incorporating the "Snyder Synthetic Unit Hydrograph Method" and the "Modified Puls" flood routing procedure. The spillway design flood selected for analysis was the Probable Maximum Flood (PMF) in accordance with recommended guidelines of the U.S. Army Corps of Engineers.

The watershed was divided into two areas for the analysis. The first portion was the 1292 acres which form the watershed for Reservoir No. 1. The second portion was the remaining 534 acres which are downstream of Reservoir No. 1. A hydrograph was developed and routed to the Reservoir No. 3 Dam for each of these areas. The routed hydrographs were then combined to arrive at the total outflow at this dam. The analysis was performed assuming that Reservoir No. 1 Dam does not fail even though the masonry portion of the dam is overtopped.

5.3 SPILLWAY CAPACITY

The chute spillway, located in the center of the embankment, has a crest 4 feet wide and 34 feet long. This length is reduced by two concrete piers each 1.5 feet wide which support the bridge for the bridle path. Stoplogs which can be placed across two of the spans and the steel superstructure for the bridge further reduce the spillway capacity. There is a drop of 24 feet between the spillway crest and the invert of the exit channel.

Hydraulically, the spillway was analyzed using a discharge coefficient, C , of 3.4 for weir flow and 0.6 for orifice flow. Due to the constrictions in the channel, the spillway length was reduced to 29 feet for the purposes of the analysis. The computed spillway discharge capacity, without stoplogs, when the water reaches the top of the dam is 1815 cfs.

The spillway without stoplogs does not have sufficient capacity for the peak outflow from either the PMF or 1/2 the PMF. For the PMF, the peak inflow is 5115 cfs and the peak outflow is 5194 cfs. For 1/2 the PMF, the peak inflow is 2557 cfs and the peak outflow is 2556 cfs.

5.4 RESERVOIR CAPACITY

Normal reservoir capacity when the water surface is at the spillway crest is 220 acre-feet. Surcharge storage capacity to the top of the dam is an additional 239 acre-feet, which is equivalent to a runoff depth of 1.6 inches over the drainage area.

5.5 FLOODS OF RECORD

No information was available regarding the occurrence of the maximum known flood.

5.6 OVERTOPPING POTENTIAL

Analysis using the PMF and 1/2 the PMF indicates that the spillway does not have sufficient discharge capacity. For a PMF peak outflow of 5194 cfs, the service spillway capacity of 1815 is only 35%. Hence, the embankment would be overtopped to a computed depth of 1.73 feet for this outflow.

For the peak outflow from the 1/2 PMF, the embankment would be overtopped to a computed depth of 0.60 feet.

5.7 EVALUATION

Using the Corps of Engineer's screening criteria for initial review of spillway adequacy, it has been determined that the embankment would be overtopped by all storms exceeding approximately 35% of the PMF. A flood wave analysis, assuming complete breaching of the embankment, indicates that water surface levels downstream of the dam could reach levels which would pose a significant danger to residents.

The spillway is, therefore, adjudged as seriously inadequate and the dam is assessed as unsafe, non-emergency.

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

Visual observations of the structure did not reveal any sign of major distress.

b. Design and Construction Data

No design computations or other data were available concerning the structural stability of the dam. The contract plans from the 1949 reconstruction of the spillway were available and sheets from these plans have been included in Appendix F.

The 1949 plans indicate that the structure has a core wall. This was in existence prior to 1949 and it is assumed that this wall was built as part of the original construction of the dam in 1908. The 1915 Conservation Commission reports indicate that the wall is concrete, but no additional information concerning the wall was available.

c. Post Construction Changes

Major modifications were made to this structure in 1949. These were the only post construction changes for which records were available.

d. Seismic Stability

This dam is located in Seismic Zone No. 1. Since the dam appears to be stable and the seismic coefficient is small, a seismic stability analysis is not warranted.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Safety

The Phase 1 inspection for New Rochelle Reservoir No. 3 revealed that the spillway is seriously inadequate and outflows from either the PMF or 1/2 the PMF would overtop the dam. This overtopping could cause breaching of the dam and the resulting floodwave would significantly increase the hazard to downstream residents. For this reason, the dam has been assessed as unsafe, non-emergency.

The remaining deficiencies on this structure, such as trees and brush growing on the embankment, are not serious enough to pose a hazard.

b. Adequacy of Information

There was a limited amount of information available for the preparation of this report. The data available was adequate with the exception of a lack of detailed descriptions of subsurface and foundation conditions and of information regarding the dimensions and composition of the core wall.

c. Need for Additional Investigations

Since the spillway was rated as seriously inadequate, additional hydrologic investigations are required to more accurately determine the site-specific characteristics of the watershed.

d. Urgency

The additional investigations which are needed should be commenced within 3 months of the date of notification of the owner that the spillway is seriously inadequate. Within 18 months of the date of notification, appropriate remedial mitigating measures should have been completed.

The minor deficiencies outlined in the next section should be corrected within 6 months of the date of notification.


7.2 RECOMMENDED MEASURES

- a. After the hydrological investigation has been completed, mitigating measures for the spillway can be determined.
- b. All trees and brush on both faces of the embankment should be cut.
- c. The section on the spillway where gunite has come off should be patched.
- d. The gully adjacent to the eastern wall of the spillway should be filled in and regraded.


- e. The reservoir drain control rod should be repaired and the drain made operational.
- f. A detailed emergency operation plan and warning system should be developed. Also, around-the-clock surveillance should be provided during periods of unusually heavy precipitation.
- g. Until the remedial mitigating measures rectifying the seriously inadequate status of the spillway have been completed, all stoplogs should be removed to provide increased spillway capacity.

APPENDIX A

PHOTOGRAPHS



SPILLWAY CHANNEL LOOKING UPSTREAM



DOWNSTREAM SLOPE OF SPILLWAY CHANNEL
SHOWING SECTION WHERE LAYER OF GUNITE IS MISSING



UPSTREAM SLOPE OF DAM WITH VALVE CONTROL
ROD EXTENDING INTO RESERVOIR



SPILLWAY CREST WITH CONCRETE STOP LOGS IN PLACE

APPENDIX B

ENGINEERING DATA CHECKLIST

Check List
Engineering Data
Design Construction Operation

Name of Dam NEW ROCHELLE RES. 3

I.D. # N.Y. 110

Item	Plans	Details	Remarks	Typical Sections
Dam	NONE			
Spillway(s)	1949 RECONSTRUCTION PLANS			
Outlet(s)	" "			
Design Reports	NONE			
Design Computations				
Discharge Rating Curves				
Dam Stability				
Seepage Studies				
Subsurface and Materials Investigations				

Item	Remarks
Construction History	None
Surveys, Modifications, Post-Construction Engineering Studies and Reports	1949 RECONSTRUCTION PLANS
Accidents or Failure of Dam Description, Reports	None
Operation and Maintenance Records Operation Manual	None

APPENDIX C

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam NEW ROCHELLE RES. No. 3

I.D. # N.Y. 110 (215-1336 LONG ISLAND)

Location: Town EASTCHESTER County WESTCHESTER

Stream Name HUTCHINSON RIVER

Tributary of _____

Longitude (W), Latitude (N) 73° 48.1' 40° 56.7'

Hazard Category C

Date(s) of Inspection 11/16/78

Weather Conditions 40° PARTLY SUNNY

b. Inspection Personnel R. WARRENDER W. LYNICK

c. Persons Contacted JOHN FAVA, DIRECTOR OF PARKS WESTCHESTER Co.
914-682-2616

d. History:

Date Constructed 1892 RECONSTRUCTED 1949

Owner WESTCHESTER Co.

Designer WESTCHESTER Co. DPW

Constructed by _____

2) Technical Data

Type of Dam EARTH WITH CONCRETE CHUTE Ogee SPILLWAY

Drainage Area 1826 ACRES

Height 31.5' Length 450'

Upstream Slope 1' ON 2 1/2 Downstream Slope 1 ON 2

2) Technical Data (Cont'd.)

External Drains: on Downstream Face _____ @ Downstream Toe _____

Internal Components:

*Impervious Core CORE WALL

Drains _____

Cutoff Type _____

Grout Curtain _____

3) Embankment

a. Crest

(1) Vertical Alignment SATISFACTORY

(2) Horizontal Alignment SATISFACTORY

(3) Surface Cracks NONE

(4) Miscellaneous BRIDLE PATH CROSSES ^{ALONG} CREST

b. Slopes

(1) Undesirable Growth or Debris, Animal Burrows TREES ON UPSTREAM SLOPE

BRUSH & VINES ON BOTH SLOPES - SMALL ANIMAL BURROW HOLES 5' ABOVE TOE
20'-30' EAST OF EAST SPILLWAY WALL

(2) Sloughing, Subsidence or Depressions ERODED WALKING PATH

1' DEEP & 3' WIDE FROM CREST DOWN TO W.S.

(3) Slope Protection ~~None~~ STONE BLOCK - COVERS MOST OF
UPSTREAM FACE

(4) Surface Cracks or Movement at Toe NONE

(5) Seepage NONE

(6) Condition Around Outlet Structure N/A

c. Abutments

(1) Erosion at Embankment and Abutment Contact EAST SIDE OF CHANNEL

MATERIAL DOWN 0-3' BELOW TOP OF EAST WALL

(2) Seepage along Contact of Embankment and Abutment NONE

(3) Seepage at toe or along downstream face NONE

d. Downstream Area - below embankment

UNDERPASS WITH STREAM OUTLET - FLOWS UNDER HUTCH. RIVER

PARKWAY

(1) Subsidence, Depressions, etc. NONE

(2) Seepage, unusual growth NONE

(3) Evidence of surface movement beyond embankment toe NONE

(4) Miscellaneous

e. Drainage System

(1) Condition of relief wells, drains, etc. _____

(2) Discharge from Drainage System _____

4) Instrumentation

(1) Monumentation/Surveys _____

(2) Observation Wells _____

(3) Weirs _____

(4) Piezometers _____

(5) Other _____

5) Reservoir

a. Slopes OKAY

b. Sedimentation NO PROBLEMS EVIDENT

6) Spillway(s) (including tail race channel)

a. General

b. Principle Spillway CONCRETE & GUNITE OGEE CHUTE

GOOD CONDITION EXCEPT FOR ONE AREA 10' X 10' WHERE
A LAYER OF GUNITE HAD COME OFF.

c. Emergency or Auxiliary Spillway NONE

d. Condition of Tail race channel CONCRETE FLUME - SATISFACTORY

e. Stability of Channel side/slopes SATISFACTORY

7) Downstream Channel

CONCRETE FLUME UNDER RAMP ROAD & HUTCHINSON
PARKWAY

a. Condition (debris, etc.) 6" LOG IN CONCRETE CHANNEL

b. Slopes VERTICAL

c. Approximate number of homes _____

8) Miscellaneous

9) Structural

- a. Concrete Surfaces GOOD EXCEPT FOR 10'X10' AREA WHERE
A LAYER OF GUNITE HAD COME OFF.
- b. Structural Cracking NONE
- c. Movement - Horizontal & Vertical Alignment (Settlement) NONE
- d. Junctions with Abutments or Embankments SATISFACTORY
- e. Drains - Foundation, Joint, Face SMALL DRAINAGE PIPES PASS
THROUGH THE CONCRETE WALLS OF THE CHANNEL. THESE
ARE PROBABLY FOR HIGHWAY DRAINAGE.
- f. Water passages, conduits, sluices
- g. Seepage or Leakage NONE

h. Joints - Construction, etc. Good

i. Foundation

j. Abutments

k. Control Gates

l. Approach & Outlet Channels HEAVY BLOCKS - PLACED WELL UP
TO CONCRETE ABUTMENT AT SPILLWAY

m. Energy Dissipators (plunge pool, etc.)

n. Intake Structures

o. Stability

p. Miscellaneous

APPENDIX D

HYDROLOGIC/HYDRAULIC

ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
	<u>USGS DATUM</u>		
1) Top of Dam	<u>130.5</u>	<u>47.4</u>	<u>498</u>
2) Design High Water (Max. Design Pool)	<u>N/A</u>	<u> </u>	<u> </u>
3) Auxiliary Spillway Crest	<u>N/A</u>	<u> </u>	<u> </u>
4) Pool Level with Flashboards	<u>N/A</u>	<u> </u>	<u> </u>
5) Service Spillway Crest	<u>123.0</u>	<u>27.6</u>	<u>220</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>N/A</u>
2) Spillway @ Maximum High Water	<u>1814.8</u>
3) Spillway @ Design High Water	<u> </u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u> </u>
5) Low Level Outlet	<u>432 37.3</u>
6) Total (of all facilities) @ Maximum High Water	<u>1814.8</u>
7) Maximum Known Flood	<u>N/A</u>

CREST:

USGS DATUM
ELEVATION: 130.5

Type: LEVEL GRASSED EARTH
Width: 6 Length: 450
Spillover SPILLWAY CHANNEL
Location CENTER OF EMBANKMENT

SPILLWAY:

PRINCIPAL

EMERGENCY

123.0 Elevation _____
CONCRETE ~~GATE~~ CHUTE Type _____
Width _____

Type of Control

✓ Uncontrolled _____

Controlled:

PROVISIONS FOR STOP LOGS ON Type _____
PORTION OF SPILLWAY (Flashboards; gate) _____

Number _____

Size/Length _____

Invert Material _____

Anticipated Length
of operating service _____

70' Chute Length _____

0 Height Between Spillway Crest
& Approach Channel Invert
(Weir Flow) _____

OUTLET STRUCTURES/EMERGENCY DRAWDOWN FACILITIES:

Type: Gate ✓ Sluice _____ Conduit _____ Penstock _____Shape: CONTROL ROD COMES TO UPSTREAM SLOPESize: 24" GATEElevations: Entrance Invert 102Exit Invert 100Tailrace Channel: Elevation 100

HYDROMETEROLOGICAL GAGES:

Type: N/A

Location: _____

Records:

Date - _____

Max. Reading - _____

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

PIPE WITH 24" GATE

DRAINAGE AREA: 1826 ACRES

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: URBAN & HEAVILY DEVELOPED

Terrain - Relief: FLAT TO MODERATE

Surface - Soil: SAND-SILT

Runoff Potential (existing or planned extensive alterations to existing
(surface or subsurface conditions)

MODERATE TO HIGH

Potential Sedimentation problem areas (natural or man-made; present or future)

NONE OBVIOUS

Potential Backwater problem areas for levels at maximum storage capacity
including surcharge storage:

POSSIBLE FLOODING OF PARKWAY

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the
Reservoir perimeter:

Location: NONE

Elevation: _____

Reservoir:

Length @ Maximum Pool .5 (Miles)

Length of Shoreline (@ Spillway Crest) _____ (Miles)

PROJECT GRID

JOB	NEW ROCHELLE RESERVOIR No. 3	SHEET NO.	1	CHECKED BY		DATE	
SUBJECT	HYDROLOGIC / HYDRAULIC COMPUTATIONS			COMPUTED BY	RLW	DATE	3/20/79
DRAINAGE AREA = 1826 ACRES = 2.85 SQ. MI.							
LAKE SURFACE AREA = 27.55 ACRES							
ELEVATION: USGS (1956) = 123							
SNYDER SYNTHETIC UNIT HYDROGRAPH:							
L = 3.60 miles $L_{CA} = 1.59$ miles							
$C_t \Rightarrow$ USE 2.0							
$t_p = C_t (L \cdot L_{CA})^{.3} = 3.37$ hours							
$t_r = \frac{t_p}{2.5} = .61$ hours (USE $\frac{1}{2}$ hr hydrograph = t_r)							
$t_{PR} = t_p + .25(t_r - t_p) = 3.34$ hours							
HR #33 PMP RAINFALL							
ZONE 1 NEAR ZONE 6 PMP RAIN = 22" (200 mi ² - 24 hr)							
6 HR 112% 24 HR 133%							
12 HR 123% 48 HR 142%							
TRSPC: T.F. = $1 - \frac{30.08}{(2.85)^{1.773}} = .750$							
LOSS DATA: INITIAL = 1.0"							
CONTINUOUS = .1"							
% OF D.A. IMPERVIOUS = 7%							
BASE FLOW = 2 cfs / SQ MILE 2 x 2.85 = 4 cfs							

PROJECT GRID

JOB	NEW ROCHELLE RESERVOIR No. 3		SHEET NO.	2	CHECKED BY	DATE
SUBJECT	HYDROLOGY / HYDRAULIC COMPUTATIONS		COMPUTED BY	RLW	DATE	3/20/79
CONIC METHOD - GENERATION OF VALUES:						
NORMAL RESERVOIR LEVEL (USGS SHEET)			123.0	ELEV		
SURFACE AREA			27.55	ACRES		
$VOLUME = \frac{h(A)}{3} = \frac{(31.5)(27.55)}{3} = 289.3 \text{ Acre-Ft}$						
APEX OF CONE:			ELEV	990		
CONIC METHOD (AREA-VOLUME)		$A = \pi R^2$	$VOL = \frac{\pi}{3} R^2 h$			
ELEV. (U.S.G.S DATUM)	RADIUS	AREA (ACRES)	h	VOL (Ac-Ft)		
130.5	811.13 ft	47.45	31.5	498		
123.0	618 ft	27.55	24	220		

PROJECT GRID

JOB	NEW ROCHELLE RESERVOIR No. 3		SHEET NO.	3	CHECKED BY	DATE
SUBJECT	HYDROLOGY / HYDRAULIC COMPUTATIONS		COMPUTED BY	RLW	DATE	3/21/79
CAPACITY WITH NO STOP LOGS IN PLACE						

Assume $H_c = 2.1'$ AND $P = 1'$
 USING FIG 249 $P/H_c = .476 \quad \therefore C_0 = 3.79$

$$L = L' - 2(NK_p + K_a)H_0$$

$K_p = 0.0$ FOR POINTED NOSE PIERS
 $K_a = .10$ ROUNDED ABUT.

ASSUMING CONCRETE PIER CONTINUOUS TO BRIDGE BEAM

$$L = (10.3 + 9 + 10.3) - 2[2(0.0) + .10]H_c$$

$$= 29.6 - .2H_c$$

ELEVATION (USGS)	H	L	H/H_c	C/C_0	C	Q
SPILLWAY CREST 123.0	0	29.6	0	-	-	0
TOP OF STOP LOGS 125.1	2.1	29.18	1	1.0	3.79	336.5
BOTTOM OF BEAM 129.4	6.4	28.4	.34	.89	3.37	1549.6

$Q = CLH^{3/2}$

PROJECT GRID

JOB	NEW ROCHELLE RESERVOIR No. 3		SHEET NO.	4	CHECKED BY		DATE	
SUBJECT	HYDROLOGY / HYDRAULIC COMPUTATIONS				COMPUTED BY	RLW	DATE	4/4/79

CAPACITY OF SPILLWAY WITH STUP LOGS IN PLACE
WATER LEVEL AT BOTTOM OF BEAM - ELEV. 129.4

BREAK SPILLWAY INTO SECTIONS

1. CENTER SECTION - LOWER

9'

2.1'

$$Q = C L H^{3/2}$$

$$L = L' - 2(NH_p + K_d)H_0$$

$$= 9 - 2(0 + 0)6$$

$$= 9$$

$$Q = 3.4(9)(6.1)^{3/2} = 461 \text{ cfs}$$

2. CENTER SECTION - UPPER

10.2'

4.9'

$$L = 10.2 - 2(0 + .2)4.9$$

$$= 8.4$$

$$Q = 3.4(8.4)(4.4)^{3/2} = 263.6 \text{ cfs}$$

3. & 4. TWO OUTSIDE SECTIONS - UPPER

11.3'

4.3

$$L = 11.3 - 2(0 + .1)(4.3)$$

$$= 10.44$$

$$Q = 3.4(10.44)^{3/2} = (326.3)(2) = 633.0 \text{ cfs}$$

TOTAL CAPACITY $Q = 461 + 263.6 + 633.0 = 1357.6 \text{ cfs}$

PROJECT GRID

JOB	NEW ROCHELLE RESERVOIR No. 3		SHEET NO.	5	CHECKED BY		DATE	
SUBJECT	HYDROLOGY/HYDRAULIC COMPUTATIONS				COMPUTED BY	RLW	DATE	4/4/79
CAPACITY OF SPILLWAY WITH NO STOP LOGS IN PLACE								
WATER LEVEL AT TOP OF DAM - ELEV. 130.5								
SUBMERGED ORIFICE								
$Q = C_a \sqrt{2gh} = (0.6)(181.76) \sqrt{2(32.2)(4.3)} = 1814.8 \text{ cfs}$								
$q = 181.76 \quad q = 32.2$ $c = 0.60 \quad h = 4.3$								
DRAIN CAPACITY - WATER AT SPILLWAY CREST								
$Q = A \sqrt{\frac{2gH}{1 + K_e + K_b + K_L + K_s}} = 3.14 \sqrt{\frac{2(32.2)(22.2)}{1 + 0 + 0.0459(1.1) + 0.5}} = 37.34 \text{ cfs}$								
$A = \pi (16)^2 = 3.14 \text{ ft}^2$ $q = 32.2$ $H = 22.2$ $K_e = 0.2 \quad K_p = 0.0459$ $K_b = 0 \quad L = 193$ $K_s = 0.05$								

PROJECT GRID

JOB	NEW ROCHELLE RESERVOIR No. 3	SHEET NO.	6	CHECKED BY		DATE	
SUBJECT	HYDROLOGY / HYDRAULIC COMPUTATIONS			COMPUTED BY	RLW	DATE	6/29/79
<p>INFORMATION OBTAINED FROM CORPS OF ENGINEER'S HUTCHINSON RIVER BASIN STUDY</p> <p>STORAGE DATA - FROM TOPOGRAPHIC MAP PREPARED BY HARRIS-TOURS ASSOCIATES</p>							
ELEVATION		SURFACE AREA (ACRES)		STORAGE (ACRE-FT)			
123		25.1		0			
124		26.9		26.0			
125		28.7		53.8			
126		30.6		83.4			
127		32.4		114.9			
128		34.2		148.2			
129.2		36.4		190.6			
130		37.9		230.3			
131		39.7		259.1			
<p>THESE VALUES ASSUME ZERO STORAGE BELOW SAILLWAY CREST. ACTUAL STORAGE BELOW THIS POINT IS ABOUT 220 ACRE-FT. (BASED ON OUR ESTIMATE).</p>							

28	Y4	123	125.1	129.4	130.5			
29	Y5	0	336	1550	1815			
30	8A	25.1	26.9	28.7	30.6	32.4	34.2	36.4 37.9 39.7
31	8E	123	124	125	126	127	128	129.2 130 131
32	88	123						
33	9D	130.5	3.087	1.5	421			
34	K							
35	A							
36	A							
37	A							
38	A							
39	A							

 FLUID HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR HONEYWELL APA 79

 THIS PROGRAM IS CURRENTLY BEING MODIFIED
 TO RUN ON THE OGS HONEYWELL SYSTEM

 PLEASE REPORT ANY UNUSUAL OPERATING PROBLEMS
 TO MIKE TILLSON (RM. 423) PH: 7-5666

RUN DATE 06/28/79
 NEW ROCHELLE RESERVOIR NO 3
 PHF WITH RATIOS NO BREACH 3
 DATE 6/14/79

JOB SPECIFICATION
 NO NHR NMN IDAY IHR IMIN METRC IPLT IPRT INSTAN
 150 1 0 0 0 0 0 0 0
 JOPER 5
 NMT LROPT TRACE
 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRATIO= 2 LRTIO= 1

RTIUS= 0.50 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH
 ISTAQ ICOMP SNAP TRSDA TRSPC JPLT JPRT INAME ISTAGE IAUTO
 1 0 0 0 0 0 0 0 0 0 0 0

HYDROGRAPH DATA

IMYDG IUMG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
 1 1 2.02 0. 2.02 0. 0. 0 1 0
 SPFE PMS R6 R12 R24 R48 R72 R96
 0. 22.00 112.00 123.00 133.00 142.00 0. 0. 0.

TRSPC COMPUTED BY THE PROGRAM IS 0.800

PRECIP DATA

LOSS DATA
 LROPT STRMR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 0 0. 0. 1.00 0. 0. 1.00 1.00 0.10 0. 0.

UNIT HYDROGRAPH DATA
 TP= 3.34 CP=0.60 NTAP= 0

RECESSION DATA

STRTO= 3.00 GRCSN= 3.00 RTIOP= 1.00
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 3.88 AND R= 3.28 INTERVALS

2.

3.

4.

5.

7.

9.

12.

17.

END-OF-PERIOD FLOW																			
MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q						
1.01	1.00	1	0.01	0.	0.01	3.	1.04	4.00	76	0.	0.	0.	3.						
1.01	2.00	2	0.01	0.	0.01	3.	1.04	5.00	77	0.	0.	0.	3.						
1.01	3.00	3	0.01	0.	0.01	3.	1.04	6.00	78	0.	0.	0.	3.						
1.01	4.00	4	0.01	0.	0.01	3.	1.04	7.00	79	0.	0.	0.	3.						
1.01	5.00	5	0.01	0.	0.01	3.	1.04	8.00	80	0.	0.	0.	3.						
1.01	6.00	6	0.01	0.	0.01	3.	1.04	9.00	81	0.	0.	0.	3.						
1.01	7.00	7	0.02	0.	0.02	3.	1.04	10.00	82	0.	0.	0.	3.						
1.01	8.00	8	0.02	0.	0.02	3.	1.04	11.00	83	0.	0.	0.	3.						
1.01	9.00	9	0.02	0.	0.02	3.	1.04	12.00	84	0.	0.	0.	3.						
1.01	10.00	10	0.02	0.	0.02	3.	1.04	13.00	85	0.	0.	0.	3.						
1.01	11.00	11	0.02	0.	0.02	3.	1.04	14.00	86	0.	0.	0.	3.						
1.01	12.00	12	0.02	0.	0.02	3.	1.04	15.00	87	0.	0.	0.	3.						
1.01	13.00	13	0.13	0.	0.13	3.	1.04	16.00	88	0.	0.	0.	3.						
1.01	14.00	14	0.16	0.	0.16	3.	1.04	17.00	89	0.	0.	0.	3.						
1.01	15.00	15	0.20	0.	0.20	3.	1.04	18.00	90	0.	0.	0.	3.						
1.01	16.00	16	0.51	0.14	0.36	8.	1.04	19.00	91	0.	0.	0.	3.						
1.01	17.00	17	0.19	0.09	0.10	22.	1.04	20.00	92	0.	0.	0.	3.						
1.01	18.00	18	0.15	0.05	0.10	43.	1.04	21.00	93	0.	0.	0.	3.						
1.01	19.00	19	0.01	0.	0.01	58.	1.04	22.00	94	0.	0.	0.	3.						
1.01	20.00	20	0.01	0.	0.01	60.	1.04	23.00	95	0.	0.	0.	3.						
1.01	21.00	21	0.01	0.	0.01	51.	1.05	0.	96	0.	0.	0.	3.						
1.01	22.00	22	0.01	0.	0.01	39.	1.05	1.00	97	0.	0.	0.	3.						
1.01	23.00	23	0.01	0.	0.01	30.	1.05	2.00	98	0.	0.	0.	3.						
1.02	0.	24	0.01	0.	0.01	23.	1.05	3.00	99	0.	0.	0.	3.						
1.02	1.00	25	0.12	0.02	0.10	18.	1.05	4.00	100	0.	0.	0.	3.						
1.02	2.00	26	0.12	0.02	0.10	16.	1.05	5.00	101	0.	0.	0.	3.						
1.02	3.00	27	0.12	0.02	0.10	17.	1.05	6.00	102	0.	0.	0.	3.						
1.02	4.00	28	0.12	0.02	0.10	19.	1.05	7.00	103	0.	0.	0.	3.						
1.02	5.00	29	0.12	0.02	0.10	20.	1.05	8.00	104	0.	0.	0.	3.						
1.02	6.00	30	0.12	0.02	0.10	22.	1.05	9.00	105	0.	0.	0.	3.						
1.02	7.00	31	0.32	0.22	0.10	29.	1.05	10.00	106	0.	0.	0.	3.						
1.02	8.00	32	0.32	0.22	0.10	53.	1.05	11.00	107	0.	0.	0.	3.						
1.02	9.00	33	0.32	0.22	0.10	93.	1.05	12.00	108	0.	0.	0.	3.						
1.02	10.00	34	0.32	0.22	0.10	142.	1.05	13.00	109	0.	0.	0.	3.						
1.02	11.00	35	0.32	0.22	0.10	182.	1.05	14.00	110	0.	0.	0.	3.						
1.02	12.00	36	0.32	0.22	0.10	211.	1.05	15.00	111	0.	0.	0.	3.						
1.02	13.00	37	1.97	1.87	0.10	285.	1.05	16.00	112	0.	0.	0.	3.						
1.02	14.00	38	2.37	2.27	0.10	501.	1.05	17.00	113	0.	0.	0.	3.						
1.02	15.00	39	2.96	2.86	0.10	902.	1.05	18.00	114	0.	0.	0.	3.						
1.02	16.00	40	7.49	7.39	0.10	1575.	1.05	19.00	115	0.	0.	0.	3.						
1.02	17.00	41	2.76	2.66	0.10	2472.	1.05	20.00	116	0.	0.	0.	3.						
1.02	18.00	42	2.17	2.07	0.10	3262.	1.05	21.00	117	0.	0.	0.	3.						
1.02	19.00	43	0.18	0.08	0.10	3576.	1.05	22.00	118	0.	0.	0.	3.						
1.02	20.00	44	0.18	0.08	0.10	3290.	1.05	23.00	119	0.	0.	0.	3.						
1.02	21.00	45	0.18	0.08	0.10	2678.	1.06	0.	120	0.	0.	0.	3.						
1.02	22.00	46	0.18	0.08	0.10	2049.	1.06	1.00	121	0.	0.	0.	3.						
1.02	23.00	47	0.18	0.08	0.10	1534.	1.06	2.00	122	0.	0.	0.	3.						
1.03	0.	48	0.18	0.08	0.10	1155.	1.06	3.00	123	0.	0.	0.	3.						
1.03	1.00	49	0.	0.	0.	874.	1.06	4.00	124	0.	0.	0.	3.						
1.03	2.00	50	0.	0.	0.	660.	1.06	5.00	125	0.	0.	0.	3.						
1.03	3.00	51	0.	0.	0.	494.	1.06	6.00	126	0.	0.	0.	3.						
1.03	4.00	52	0.	0.	0.	366.	1.06	7.00	127	0.	0.	0.	3.						
1.03	5.00	53	0.	0.	0.	270.	1.06	8.00	128	0.	0.	0.	3.						
1.03	6.00	54	0.	0.	0.	199.	1.06	9.00	129	0.	0.	0.	3.						
1.03	7.00	55	0.	0.	0.	147.	1.06	10.00	130	0.	0.	0.	3.						
1.03	8.00	56	0.	0.	0.	108.	1.06	11.00	131	0.	0.	0.	3.						
1.03	9.00	57	0.	0.	0.	78.	1.06	12.00	132	0.	0.	0.	3.						
1.03	10.00	58	0.	0.	0.	55.	1.06	13.00	133	0.	0.	0.	3.						
1.03	11.00	59	0.	0.	0.	37.	1.06	14.00	134	0.	0.	0.	3.						
1.03	12.00	60	0.	0.	0.	18.	1.06	15.00	135	0.	0.	0.	3.						

1.01	18.00	18	0.15	0.02	0.10	33.	1.04	21.00	93	0.	0.	0.	0.	0.	1.
1.01	19.00	19	0.01	0.	0.01	33.	1.04	22.00	94	0.	0.	0.	0.	0.	3.
1.01	20.00	20	0.01	0.	0.01	25.	1.04	23.00	95	0.	0.	0.	0.	0.	3.
1.01	21.00	21	0.01	0.	0.01	17.	1.05	0.	96	0.	0.	0.	0.	0.	3.
1.01	22.00	22	0.01	0.	0.01	12.	1.05	1.00	97	0.	0.	0.	0.	0.	3.
1.01	23.00	23	0.01	0.	0.01	9.	1.05	2.00	98	0.	0.	0.	0.	0.	3.
1.02	0.	24	0.01	0.	0.01	7.	1.05	3.00	99	0.	0.	0.	0.	0.	3.
1.02	1.00	25	0.12	0.02	0.10	6.	1.05	4.00	100	0.	0.	0.	0.	0.	3.
1.02	2.00	26	0.12	0.02	0.10	7.	1.05	5.00	101	0.	0.	0.	0.	0.	3.
1.02	3.00	27	0.12	0.02	0.10	9.	1.05	6.00	102	0.	0.	0.	0.	0.	3.
1.02	4.00	28	0.12	0.02	0.10	10.	1.05	7.00	103	0.	0.	0.	0.	0.	3.
1.02	5.00	29	0.12	0.02	0.10	11.	1.05	8.00	104	0.	0.	0.	0.	0.	3.
1.02	6.00	30	0.12	0.02	0.10	11.	1.05	9.00	105	0.	0.	0.	0.	0.	3.
1.02	7.00	31	0.32	0.22	0.10	21.	1.05	10.00	106	0.	0.	0.	0.	0.	3.
1.02	8.00	32	0.32	0.22	0.10	46.	1.05	11.00	107	0.	0.	0.	0.	0.	3.
1.02	9.00	33	0.32	0.22	0.10	73.	1.05	12.00	108	0.	0.	0.	0.	0.	3.
1.02	10.00	34	0.32	0.22	0.10	102.	1.05	13.00	109	0.	0.	0.	0.	0.	3.
1.02	11.00	35	0.32	0.22	0.10	186.	1.05	14.00	110	0.	0.	0.	0.	0.	3.
1.02	12.00	36	0.32	0.22	0.10	407.	1.05	15.00	111	0.	0.	0.	0.	0.	3.
1.02	13.00	37	1.97	1.87	0.10	701.	1.05	16.00	112	0.	0.	0.	0.	0.	3.
1.02	14.00	38	2.37	2.27	0.10	1166.	1.05	17.00	113	0.	0.	0.	0.	0.	3.
1.02	15.00	39	2.96	2.86	0.10	1720.	1.05	18.00	114	0.	0.	0.	0.	0.	3.
1.02	16.00	40	7.49	7.39	0.10	1846.	1.05	19.00	115	0.	0.	0.	0.	0.	3.
1.02	17.00	41	2.76	2.66	0.10	1539.	1.05	20.00	116	0.	0.	0.	0.	0.	3.
1.02	18.00	42	2.17	2.07	0.10	1109.	1.05	21.00	117	0.	0.	0.	0.	0.	3.
1.02	19.00	43	0.18	0.08	0.10	725.	1.05	22.00	118	0.	0.	0.	0.	0.	3.
1.02	20.00	44	0.18	0.08	0.10	476.	1.06	23.00	119	0.	0.	0.	0.	0.	3.
1.02	21.00	45	0.18	0.08	0.10	317.	1.06	0.	120	0.	0.	0.	0.	0.	3.
1.02	22.00	46	0.18	0.08	0.10	217.	1.06	1.00	121	0.	0.	0.	0.	0.	3.
1.02	23.00	47	0.18	0.08	0.10	150.	1.06	2.00	122	0.	0.	0.	0.	0.	3.
1.03	0.	48	0.18	0.08	0.10	99.	1.06	3.00	123	0.	0.	0.	0.	0.	3.
1.03	1.00	49	0.	0.	0.	62.	1.06	4.00	124	0.	0.	0.	0.	0.	3.
1.03	2.00	50	0.	0.	0.	38.	1.06	5.00	125	0.	0.	0.	0.	0.	3.
1.03	3.00	51	0.	0.	0.	18.	1.06	6.00	126	0.	0.	0.	0.	0.	3.
1.03	4.00	52	0.	0.	0.	10.	1.06	7.00	127	0.	0.	0.	0.	0.	3.
1.03	5.00	53	0.	0.	0.	6.	1.06	8.00	128	0.	0.	0.	0.	0.	3.
1.03	6.00	54	0.	0.	0.	5.	1.06	9.00	129	0.	0.	0.	0.	0.	3.
1.03	7.00	55	0.	0.	0.	4.	1.06	10.00	130	0.	0.	0.	0.	0.	3.
1.03	8.00	56	0.	0.	0.	3.	1.06	11.00	131	0.	0.	0.	0.	0.	3.
1.03	9.00	57	0.	0.	0.	3.	1.06	12.00	132	0.	0.	0.	0.	0.	3.
1.03	10.00	58	0.	0.	0.	3.	1.06	13.00	133	0.	0.	0.	0.	0.	3.
1.03	11.00	59	0.	0.	0.	3.	1.06	14.00	134	0.	0.	0.	0.	0.	3.
1.03	12.00	60	0.	0.	0.	3.	1.06	15.00	135	0.	0.	0.	0.	0.	3.
1.03	13.00	61	0.	0.	0.	3.	1.06	16.00	136	0.	0.	0.	0.	0.	3.
1.03	14.00	62	0.	0.	0.	3.	1.06	17.00	137	0.	0.	0.	0.	0.	3.
1.03	15.00	63	0.	0.	0.	3.	1.06	18.00	138	0.	0.	0.	0.	0.	3.
1.03	16.00	64	0.	0.	0.	3.	1.06	19.00	139	0.	0.	0.	0.	0.	3.
1.03	17.00	65	0.	0.	0.	3.	1.06	20.00	140	0.	0.	0.	0.	0.	3.
1.03	18.00	66	0.	0.	0.	3.	1.06	21.00	141	0.	0.	0.	0.	0.	3.
1.03	19.00	67	0.	0.	0.	3.	1.06	22.00	142	0.	0.	0.	0.	0.	3.
1.03	20.00	68	0.	0.	0.	3.	1.06	23.00	143	0.	0.	0.	0.	0.	3.
1.03	21.00	69	0.	0.	0.	3.	1.07	0.	144	0.	0.	0.	0.	0.	3.
1.03	22.00	70	0.	0.	0.	3.	1.07	1.00	145	0.	0.	0.	0.	0.	3.
1.03	23.00	71	0.	0.	0.	3.	1.07	2.00	146	0.	0.	0.	0.	0.	3.
1.04	0.	72	0.	0.	0.	3.	1.07	3.00	147	0.	0.	0.	0.	0.	3.
1.04	1.00	73	0.	0.	0.	3.	1.07	4.00	148	0.	0.	0.	0.	0.	3.
1.04	2.00	74	0.	0.	0.	3.	1.07	5.00	149	0.	0.	0.	0.	0.	3.
1.04	3.00	75	0.	0.	0.	3.	1.07	6.00	150	0.	0.	0.	0.	0.	3.

SUM 24.99 21.29 3.71 11794.7
(635.1) (341.1) (94.1) 333.97)

PEAK 1046. TOTAL VOLUME 11789.
6-HOUR 1349. 72-HOUR 468. 24-HOUR 468. 101.

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS	2956.	1928.	792.	274.		19924.
CMS	72.	55.	22.	8.		564.
INCHES		6.29	10.34	10.71		10.86
MM		159.81	262.57	272.15		275.30
AC-FT		956.	1570.	1628.		1647.
THOUS CU M		1179.	1937.	2008.		2031.

STATION 2, PLAN 1, RATIO 2
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW

[illegible]

STORAGE

[illegible]

STAGE

[illegible]

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS	
				RATIO 1	RATIO 2
				0.50	1.00
HYDROGRAPH AT	1	2.02	1	1788.	3976.
	(0.00)	(90.63)(101.25)(
HYDROGRAPH AT	2	0.83	1	923.	1846.
	(0.00)	(26.14)(52.27)(
2 COMBINED		2.85	1	2557.	5115.
	(0.00)	(72.42)(144.84)(
ROUTED TO	2	2.85	1	2556.	5194.
	(0.00)	(72.37)(147.08)(

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PHF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	123.00	123.00	130.50								
	0.	0.	239.								
	0.	0.	1815.								
				0.50	131.10	0.60	263.	2556.	3.00	43.00	0.
				1.00	132.23	1.73	309.	5144.	7.00	42.00	0.

FLOID HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79
MODIFIED FOR HONEYWELL APR 77

THIS PROGRAM IS CURRENTLY BEING MODIFIED
TO RUN ON THE OGS MONEYWELL SYSTEM

PLEASE REPORT ANY UNUSUAL OPERATING PROBLEMS
TO MIKE TILLSON (RM. 423) PH: 7-9666

1 A NEW RUCHELLE RESERVOIR NO 3
2 A PMF WITH RATIOS WITH BREACH

[illegible]

1	2	1	1	1
---	---	---	---	---

11

10	M	1	2.02	0	1

[illegible]

Year	Number of cases	Percentage of total cases
1913	3,349	9.0
1914	3,349	9.0

13	X	0	2	
14	K1	INFLOW HYDROGRAPH 2		.

[illegible]

67

	1	3	3	x	12
--	---	---	---	---	----

23 K1 COMBINE HYDROGRAPHS

24 K 1 2
25 K1 COMBINE HYDROGRAPH AT DAM 3 WITH BREAK

A vertical ruler with markings from 1 to 10. The markings are small vertical lines, and the numbers are printed to the right of the ruler.

[illegible]

60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75
Y6	Y7	Y7	K	K1	Y	Y1	Y6	Y7	Y7	K	A	A	A	A	A
.05	0	1400	1	LOCATION		1	.05	0	600	99					
.05	90	70	11790	NARROW			.05	90	70						
.05	200	1700		SECTION			.05	40	700						
61	80	90			1		60	80	75						
3200	400	2000			1		90	110	800						
70	70	100					1000	70	80						
.008	900		1				.001	200							
61	1000						60	440							

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.50	131.07	131.07	123.00	123.00	130.50	46.00	43.00
1.00	131.66	131.66	0.	0.	239.	46.00	41.00
			0.	0.	1815.		

PLAN 1 STATION 4040

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.50	10674.	99.2	46.00
1.00	10686.	99.3	43.00

PLAN 1 STATION 7540

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.50	3709.	105.1	46.00
1.00	9451.	107.7	43.00

PLAN 1 STATION 7590

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.50	3696.	91.8	46.00
1.00	9452.	92.7	43.00

PLAN 1 STATION 10790

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.50	5947.	65.0	47.00
1.00	8941.	65.7	43.00

PLAN 1 STATION 11790

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.50	6052.	66.6	47.00
1.00	8653.	68.0	43.00

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO 1	RATIO 2
				0.50	1.00
HYDROGRAPH AT	1	2.02 (0.00)	1	1788. (50.63)	3576. (101.25)
HYDROGRAPH AT	2	0.83 (0.00)	1	923. (26.14)	1846. (52.27)
2 COMBINED		2.85 (0.00)	1	2557. (72.42)	5115. (144.84)
ROUTED TO	2	2.85 (0.00)	1	1085. (302.57)	1085. (302.57)
ROUTED TO	4040	2.85 (0.00)	1	10674. (302.26)	10686. (302.61)
ROUTED TO	7540	2.85 (0.00)	1	5705. (161.54)	9451. (267.62)
ROUTED TO	7590	2.85 (0.00)	1	5696. (161.30)	9452. (267.64)
ROUTED TO	10790	2.85 (0.00)	1	5947. (168.39)	8941. (253.18)
ROUTED TO	11790	2.85 (0.00)	1	6052. (171.36)	8653. (245.02)

APPENDIX E

REFERENCES


APPENDIX E

REFERENCES

- 1) U.S. Department of Commerce, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May 1961.
- 2) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 3) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.
- 4) Elwyn E. Seelye, Design, 3rd edition, John Wiley and Sons, Inc., 1960.

APPENDIX F

DRAWINGS



DAM SITE

VICINITY MAP
NEW ROCHELLE RESERVOIR
No. 3 DAM

(NOTICE: After filling out one of these forms as completely as possible for each dam in your district, return it at once to the Conservation Commission, Albany.)

STATE OF NEW YORK
CONSERVATION COMMISSION
ALBANY

DAM REPORT

June 22nd, 1915
(Date)

CONSERVATION COMMISSION,

DIVISION OF INLAND WATERS.

GENTLEMEN:

I have the honor to make the following report in relation to the structure known as the Reservoir No 3 New Rochelle Water Co. Dam.

This dam is situated upon the Hutchinson River
(Give name of stream)
in the Town of East Chester, Westchester County,
about 3-4 miles from the ~~Village~~ or City of New Rochelle
(State distance)
The distance up stream from the dam, to the No 1 dam
(Up or down) (Give name of nearest important stream or of a bridge)
is about 1/2 mile
(State distance)


The dam is now owned by W. R. Water Co. (Julien Estate)
(Give name and address in full)
and was built in or about the year 1908, and was extensively repaired or reconstructed during the year _____

As it now stands, the spillway portion of this dam is built of Concrete Gravel + 4"x10" Timber
(State whether of masonry, concrete or timber)
and the other portions are built of Concrete Sea. to fill + bank
(State whether of masonry, concrete, earth or timber with or without rock fill)



As nearly as I can learn, the character of the foundation bed under the spillway portion of the dam is Rock and under the remaining portions such foundation bed is Rock

215 B

(In the space below, make a third sketch showing the general plan of the dam, and its approximate position in relation to buildings or other conspicuous objects in the vicinity.)



(In the space below, make one sketch showing the form and dimensions of a cross section through the spillway or waste-weir of this dam, and a second sketch showing the same information for a cross section through the other portion of the dam. Show particularly the greatest height of the dam above the stream bed, its thickness at the top, and thickness at the bottom, as nearly as you can learn.)



The total length of this dam is 450 feet. The spillway or waste-weir portion, is about 25 feet long, and the crest of the spillway is about 3 feet below the top of the dam.

The number, size and location of discharge pipes, waste pipes or gates which may be used for drawing off the water from behind the dam, are as follows: Two 12" pipes and a 24" pipe all leading into a 42" pipe

At the time of this inspection the water level above the dam was 2 ft. 6 in. below the crest of the spillway.

(State briefly, in the space below, whether, in your judgment, this dam is in good condition, or bad condition, describing particularly any leaks or cracks which you may have observed.)

This dam was also in Excellent condition and well taken care of. Should a rupture of the dam occur the flow would no doubt be taken care of by the reservoir just below it (No 2)


Reported by

L. D. Seymour
(Signature)

Box 178

(Address—Street and number, P. O. Box or R. F. D. route)

Walcott N. Y.
(Name of place)



2

WHERE NECESSARY, ON THE UPS
119.0± AND 126.5±, RELAY THE EX
AS DIRECTED UNDER ITEM NO. 76.

120

125

ITEM NO. 2

CORRECTION OF EARTH DAM

PLACE 12 DRY
STONE PAVING
ITEM NO. 76.

125

120

REMOVE ALL TREE
SIMILAR GROWTH ON
THIS AND INDICATED AREAS OF
FILL ALL HOLES WITH
SELECTED MATERIAL, SPREAD
AND SEED. INCLUDED UNDER
NOS. 2, 40 AND 71.

EASTCHESTER SANITARY SEWER

RESERVOIR NO.2

ON THE UPSTREAM FACE OF DAM BETWEEN
THE EXISTING 12' DRY STONE PAVING
AND THE ONE HAYWARD EACH AS DIRECTED

START OF CONTRACT

PLACE 18' DRY PAVING
ITEM NO. 79

RECONSTRUCT EXISTING
DAM SPILLWAY.

ALL TREES, SHRUBS AND OTHER
GROWTH ON DAM SLOPES WITHIN
AREAS OR AS DIRECTED.
FILL HOLES WITH COMPACTED,
SPREAD TOP SOIL, GRADE,
INCLUDED UNDER ITEMS
68 AND 71.

FROM WEBSTER

PLUG
INV. EL. 98.8±
INV. EL. 98.0±
24" VALVE
INV. EL. 98.0±
12" VALVE
EXISTING VALVE STEM
INV. EL. 107.0±
INV. EL. 113.5±

42" BLOWOFF PIPE

0+90
+10
INV. EL. 98.8±

110

105

110

115

1
REPAINTING
OUTLET PIPING
M NO. 91

4
NOTE: THE OUTLET PIPING AS
SHOWN, IS FROM AN OLD
PLAN THE COMPLETENESS
OR ACCURACY OF WHICH
IS UNCERTAIN, AND IS ONLY
INTENDED TO TYPIFY THE
CONDITIONS WHICH MAY BE
FOUND.

120
RELAY THE EXISTING DRY STONE PAVING
AS DIRECTED. ITEM 125 NO. 78.

CORRECTION OF EARTH DAM

ITEM NO. 2


115

WEBSTER AVE

PARKWAY

NORTHBOUND

1
EXIT TO WEBSTER




15


LOCATION MAP
1 INCH=1000 FEET

APPROVED FOR: DATE: May 20
WESTCHESTER COUNTY PARK COMMISSION

[Signature]
GENERAL SUPERINTENDENT

MADE BY G.J.S. MAR. 1929.
TRACED BY G.J.S. APR. 1929.
CHECKED BY J.W.M.





CONSTRUCT NEW
CONCRETE CHANNEL

RIVER

GENERAL PLAN

SCALE 1 IN = 20 FT.

CONSTRUCT NEW
HYDRAULIC JUMP
STRUCTURE

COUNTY TRUNK SEWER

BRIDGE

APPROVED:

DATE: May 20 1949

James C. L...
COMMISSIONER OF PUBLIC WORKS

RECOMMENDED: DATE: May 23 1949
WESTCHESTER COUNTY DEPT. OF PUBLIC WORKS

Charles R. Sanfield

PRINCIPAL ASSISTANT ENGINEER

PARK

EXIT TO WEBSTER AVENUE

AL PLAN
LE 1 IN = 20 FT.

WESTCHESTER COUNTY
DEPARTMENT OF PUBLIC WORKS
DIVISION OF ENGINEERING
PLANS
FOR RECONSTRUCTION OF SPILLWAY
AND
IMPROVEMENT OF CHANNEL
AT
RESERVOIRS NO. 2 & NO. 1 - HUTCHINSON RIVER
IN
TOWN OF EASTCHESTER AND
CITY OF NEW ROCHELLE
N.Y.

APRIL 1949

May 2, 1949

DEPARTMENT OF PUBLIC WORKS

STADIUM OF CONTRACT


BASE LINE

SECTION X-X

COMPLETED FILE
ITEM NO. 46

EXISTING RIP-RIP
TO SUB-GRADE,
18" STONE PAVING,
S NOS. 3 & 79.

VE PORTION OF
ING CORE-WALL AND
CONCRETE SPILLWAY.
ALLS EXCAVATE TO
DE, REPLACE AS
DIRECTED.
4, 3, 14, 15, 18 & 20



DOVE SPILLWAY
W WALLS AS
ITEM NOS. 4, 14, 18, 19 & 20.

WAY WALLS
BRIDGE.

LADE OF NEW
NO. 5.

AGE
ON
NO. 70

PL
SCALE 1 IN


COMPACTED
ITEM


DRIVE


ACCESS

TYPICAL WEEP HOLE
TO WEEP HOLE DRAIN
SEE DETAIL ITEM 6

0
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100







MADE BY CJS Apr. 1949
TRACED BY J.S. & G.S.
CHECKED BY JHM

REMOVE EXISTING PAVING, CONSTRUCT NEW WALLS AS SHOWN OR DIRECTED, ITEM NOS. 4, 14, 18, 19, 20

EAST SIDE EL. 108.7 } TOP OF NEW SPILLWAY WALLS
WEST SIDE EL. 108.7 } AT ACCESS BRIDGE.

UNDERSIDE OF BRIDGE ON SECTION X-X
ELEV. 106.2

REMOVE 42" C.I. PIPE ABOVE GRADE OF NEW
SPILLWAY AND CHANNEL. ITEM NO. 5.


WEBSTER AVENUE ACCESS BRIDGE
SOUTHBOUND TRAFFIC ONLY

UNDERSIDE OF BRIDGE ON SECTION X-X
ELEV. 105.7

INCORPORATE DRAIN PIPES IN NEW
CHANNEL WALLS. BOTH SIDES.

REMOVE WOOD BRIDGE PATH BRIDGE
INTACT AND REPLACE TO POSITION
AS SHOWN OR DIRECTED. ITEM NO. 70

PLAN
SCALE 1 IN. = 10'



N
FEET.

NOTE: ON THIS PL
STRUCTURE
PROPOSED

HUTCHINSON RIVER PARKWAY

SOUTHBOUND

NORTHBOUND

UNDERSIDE OF BRIDGE ON SECTION X-X ELEV. 110.0

CONCRETE CHANNEL WALL
BY RUSTIC FENCE (SEE
SOUTHERLY END. ITEM

NEW CHANNEL WALLS

DEEP HOLES

SPRINGING LINE OF BRIDGE EL. 101.0

BOTTOM

GRADE 0.50 %

BRIDGE FOOTINGS ELEV. 94.0

104.0

97.31
97.25

95.25

2+0

2+28

2+50

N X-X

1 IN. = 5 FEET.

1 IN. = 10 FEET.

RECOMMENDED: DATE: May 20, 1949.
WESTCHESTER COUNTY DEPT. OF PUBLIC WORKS


Charles A. Sanfill

PRINCIPAL ASSISTANT ENGINEER


END OF CONTRACT.

NOTE: ON THIS PLAN, IN GENERAL, DASH LINES SHOW EXISTING STRUCTURES AND TOPOGRAPHY, SOLID LINES DENOTE PROPOSED WORK INCLUDED UNDER THIS CONTRACT.

CONCRETE CHANNEL WALLS, BOTH SIDES, TO BE SURMOUNTED BY RUSTIC FENCE (SEE DETAIL), FROM ACCESS BRIDGE TO SOUTHERLY END. ITEM NO. 73-A.



1



1


2


B

F

ITS OF EXCAVATION WITH REMOVAL OF
-RAP AND REPLACEMENT WITH
STONE PAVING. ITEMS NO. 3 & 79.

E





RELAY EXISTING 12" DRY STONE PAVING
AS DIRECTED. ITEM NO. 78.

EXISTING VALVE BOX

COREWALL AT ELEV. 123.5

COREWALL AT ELEV. 123.5



119.0

121

123

127

120

125

127

125

119.0


AD-A075 890

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/G 13/2
NATIONAL DAM SAFETY PROGRAM. NEW ROCHELLE RESERVOIR NUMBER 3 DA--ETC(U)
SEP 79 G KOCH DACW51-79-C-0001

NL


UNCLASSIFIED

2 OF 2
AD-
A075890




END
DATE
FILMED

11-79
DDC






NATIONAL BUREAU OF STANDARDS
MICROCOPY RESOLUTION TEST CHART

1
4
CONSTRUCT NEW RUSTIC
TIMBER SUPPORT
ITEM NO. 90.



SECTION D-D






CROSS HATCHING INDICATES MINIMUM
LIMITS OF CONCRETE TO BE REMOVED
UNDER ITEM NO. 4.

MADE BY *CLS Apr 1949*
TRACED BY *CLS Apr 1949*
CHECKED BY *JMT*

5


STOP LOG PIERS

B



PLAN

SCALE $\frac{1}{4}'' = 1 \text{ FT.}$




TOP OF EXISTING
PIER ELEV. 127.4

REMOVE EX
CONCRETE
OR TO LIN
AS DIRECT
FINISHED

TOP OF
EXISTING SPILLWAY ELEV. 123.50


FINISHED ELEV. 120

NEW





{ REMOVE EXISTING TIMBERS SUPPORTING
VALVE ROD. SHORTEN VALVE ROD AS DIRECTED.
CONSTRUCT NEW RUSTIC TIMBER SUPPORT.
THIS WORK INCLUDED UNDER ITEM NO.90.

EXISTING PIER TO
OF COREWALL
ES AS SHOWN OR
ED IN FIELD.
ELEV. 127.50±




EXISTING GROUND SURFACE 127.6±
TOP OF EXISTING COREWALL ELEV. 126.4±



RECOMMENDED
WESTCHESTER COUNTY DEPT. OF PUBLIC WORKS
Chas. W. Sanfield
PRINCIPAL ASSISTANT ENGINEER

DATE: May 20, 1949


7



TING
DIRECTED.
SUPPORT.
NO. 90.

SECTION C-C

RFACE 127.5±
WALL ELEV. 126.4±



SECTION B-B

1

8

